

NEW PARTS LIST				
QTY.	SYMBOL	DESCRIPTION	INSTALLATION NOTES	MOUNTING NOTES
1	FCP	FIRE ALARM CONTROL PANEL NFS-3030D, WITH ACCESSORIES (2) CHS-M4, (5)LEM-320, (5) LCM, (1)AMPS-24E, (1)BB-200	SUPPLIED WITH ENCLOSURE	72" A.F.F. TO TOP
2	FCPS	REMOTE POWER SUPPLY FCPS-24S8	SUPPLIED WITH ENCLOSURE	DETERMINE IN FIELD
238	SD	SMOKE DETECTOR FSP-851	1900 BOX	ON CEILING / UNDER FLOOR
48	LD	LASER SMOKE DETECTOR FLS-751	1900 BOX	ON CEILING / UNDER FLOOR
5	S	PULL STATION NBG-12LX	1900 BOX	48" A.F.F. TO CENTER
6	D	HEAT DETECTOR, 135° FIXED TEMP. FST-851	1900 BOX	ON CEILING
24	DD	DUCT DETECTOR DH100ACDCL WP WITH ST-10 SAMPLE TUBE	MOUNT ON RETURN SIDE OF HVAC UNIT TIE INTO BUILDING 120V POWER	
24	RTS	REMOTE TEST STATION RTS-451	SINGLE GANG BOX	DETERMINE IN FIELD
20	MMX	ADDRESSABLE SINGLE MONITOR MODULE FMM-1	1900 BOX	DETERMINE IN FIELD
24	R	ADDRESSABLE SINGLE RELAY MODULE FRM-1	1900 BOX	DETERMINE IN FIELD
1	CR	ADDRESSABLE SINGLE CONTROL MODULE FCM-1	1900 BOX	DETERMINE IN FIELD
33	SV	SPEAKER STROBE SP2R1224MC	DEEP 1900 BOX	80"-96" A.F.F. TO CENTER
12	SV ^C	SPEAKER STROBE SP2C24115	DEEP 1900 BOX	ON CEILING
4	H	DOOR HOLDER FM998	BY OTHERS TIE INTO BUILDING 120V POWER	DETERMINE IN FIELD
4	T	FIREMAN'S PHONES	SUPPLIED WITH ENCLOSURE	DETERMINE IN FIELD
3	V	STROBE SW	1900 BOX	80"-96" A.F.F. TO CENTER

**CONTRACTOR IS RESPONSIBLE TO VERIFY DEVICE COUNTS AND MODEL NUMBERS

EXISTING PARTS LIST		
QTY.	SYMBOL	DESCRIPTION
1	FAA	FIRE ALARM REMOTE ANNUCIATOR LCD-80
472	SD	SMOKE DETECTOR SDX-551
20	S	PULL STATION NBG-101L
21	D	HEAT DETECTOR, 135° FIXED TEMP. FDX-551
31	DD	DUCT DETECTOR DHX-501
31	RTS	REMOTE TEST STATION RTS-451
51	MMX	ADDRESSABLE SINGLE MONITOR MODULE FMM-1
34	CR	ADDRESSABLE SINGLE CONTROL MODULE CMX-2
95	SV	SPEAKER STROBE FARADAY 2608B-U-14-24V
10	V	STROBE FARADAY 5521B-U-14-24DC
11	T	FIREMAN'S PHONES

**INFORMATION RECORDED ON AS-BUILT FIRE ALARM DRAWINGS DATED 5-19-95